



LANDFORD STONE

Templating

Replacement Tops

All base units must be firmly fixed to the walls and levelled.

Please arrange for all existing worktops to be removed prior to the Templater's arrival. This includes the removal of sinks and hobs.

Sinks/Bowls

All under mounted, ceramic or cast iron sinks must be supported in the base unit on a framework/cradle.

Steel sinks preferably mounted as above but these can be suspended from the granite if necessary. Steel sinks must be mounted in cradle for Caesarstone worktops.

Please note that we do not suspend bowls from 20mm granite or 20+20mm.

Inset sinks must be on site.

Taps/Drinking Water Filter

Taps should be on site but if this is not possible all relevant information should be available to the Templater i.e. Hole size and tap throw.

Hobs

All hobs should be made available at the time of the template.

Accurate cut out dimensions must be supplied if hobs are not available.

AGA

Unless your AGA/Rayburn etc. is fitted in the final position we cannot template to an acceptable standard and therefore no work can be undertaken until this is achieved.

Range Cookers

All range type cookers to be in their final position or on site.

Accurate dimensions must be available if this is not possible.

Please note that there are certain situations which could prevent us from completing your template if the range cooker is not in position.

Breakfast Bars

All large Breakfast Bars or seating areas must have a minimum of 18mm MDF or plywood sub-base in position at time of template. The sub-base can be 50/100mm smaller than the final granite dimensions. The maximum unsupported overhang allowed is 300mm, any larger will require leg or corbel supports.



If our Templater cannot complete the template due to problems on site, it will probably necessitate an additional visit, which may incur delay and extra costs. If you have any technical questions regarding the above, please do not hesitate to call and ask for a Technical Adviser or a Templater.